कार्यालय अधीक्षण अभियन्ता (तकनीकी)

33/11 केवी फजलगंज उपकेन्द्र, केस्को, कानपुर

पत्रांक सं0 / 744 अधी०अभि०(तक०) / लेखा / निविदा / 24–25

दिनांक: 03/04/2025

ई—निविदा संख्या 10/S.E.Tech./2024-25 को पुनः अपलोड किये जाने की सूचना

एतद्द्वारा सूचित किया जाता है कि ई—िनिविदा संख्या 10/S.E.Tech./2024-25 (केस्को कानपुर के सहायक अभियन्ता—प्रथम, 33 केवी एण्ड इलेक्ट्रिकल सेफ्टी, केस्को कानपुर के कार्यक्षेत्र में स्थापित 33 के.वी. और 11 के.वी. अपरगामी व भूमिगत लाइनों तथा 33/11 के.वी. विद्युत उपकेन्द्रो में होने वाले आकिस्मक मेजर ब्रेकडाउनों के फलस्वरुप बाधित विद्युत आपूर्ति की तत्काल बहाली हेतु ब्रेकडाउनों को अटैण्ड करने एवं उनकी समय—समय पर आकिस्मक मरम्प्त व अनुरक्षण के साथ—साथ पूर्ण जमा एवं प्रणाली सुधार के अन्तर्गत छोटे—छोटे आकिस्मक कराये जाने के कार्यो हेतु), जो दिनांक 28.03.2025 को खोली जानी है, में किसी भी निविदादाता के द्वारा निविदा में प्रतिभाग न करने के कारण उक्त निविदा को निर्धारित दिनांक एवं समयाविध में ही विस्तारित किया जाना था, परन्तु तकनीकी कारणोवश निविदा विस्तारित नहीं हो सकी।

अतः उक्त ई–निविदा को यू०पी० एन.आई.सी. / केस्को की ई–टेंडरिंग वेबसाईट https://etender.up.nic.in पर पुनः अपलोड किये जाने एवं तदनुसार निविदा खोले जाने की दिनांक 16.04.2025 निर्धारित की जाती है। ई–निविदा की शेष नियम व शर्ते यथावत् रहेगीं।

अधीक्षण अभियन्ता

्र (तकनीकी)

'<u>राष्ट्रहित में बिजली बचाए</u>ँ"



कार्यालय अधीक्षण अभियन्ता (तकनीकी)

33/11 केवी फजलगंज उपकेन्द्रे, केस्को, कानपुर

ई मेल - se.technical@kesco.org.in

PUBLICATION OF TENDER NOTICE KANPUR ELECTRICITY SUPPLY COMPANY LIMITED, KANPUR

Tender Number	T-10/S.E.Tech/2024-25				
Name Of Work	Work of Attending breakdowns, construction, rearrangement, shifting, replacement/repairing of damaged poles etc. of lines and Sub-station apparatus against M and R, Small S.I. and Deposit works of 33KV and 11KV O/H and U/G lines and Substation including loading, unloading, carriage, dismantling & erection of power transformer, oil centrifusing (1.5 to 10 MVA) and all related works under the area of Assistant Engineer-Ist, 33 KV & Electrical Safety, Kesco Kanpur				
Nature Of Tender	M&R				
Estimated Amount (Without GST)	Rs. 32.50 Lac				
Tender Form Cost (Inclusive of GST)	Rs. 3540.00 (Non Refundable)				
Earnest Money Deposit (1% Of Estimated Cost)	Rs. 35,000.00 (Refundable) (Round Off)				
Last Date & Time of Purchase Of Tender	20.03.2025, 14:00 Hrs.				
Last Date & Time Of Tender Submission	20.03.2025, 14:00 Hrs.				
Tender Opening Due Date & Time For Part-One	21.03.2025, 14:00 Hrs.				
Note: Each and every form should be filled full and properly otherwise the same may be rejected without giving any notice.					

(Pravesh Kumar)
SUPERINTENDING ENGINEER (Tech.)
KESCo.

INSTRUCTIONS TO TENDERERS AGAINST TENDER NO. ET-10/S.E.Tech/2024-25, OPENING ON 21.03.2025.

- The tender will be submitted in two parts, which will be received upto 14:00 Hours on 20.03.2025 and part –I will be opened at 14:00 Hours on 21.03.2025 in presence of Tenderers/ Their Representatives.
- 2. Part I of tender will contain the following documents:-
- a. Tender fee amounting to Rs. 3540.00 (Inclusive of GST) will be deposited through RTGS/NEFT in Indian Bank Account Number 7723508014 (IFSC Code- IDIB000K587). Properly filled by Contractor as per Part-I(B)
- b. Earnest Money (1% of Estimated Cost) amounting to Rs. 35,000.00 will be deposited through NEFT/RTGS in Indian Bank Account Number 7723508014 (IFSC Code-IDIB000K587). Properly filled by Contractor as per Part-I(B).
- c. All technical and financial requirement of Eligibility Criteria/Pre-Qualifying Requirements as per Ref. No. 1632/C.M.U.(D)/S.E.-1 Dated 31-07-2024.
- **d.** Schedule 'C', Part-I (A) & (B) of tender document duly filled and signed with stamp of the tenderer.
- 3. Other terms & Conditions of tenderer if any.
- 4. Part-II of tender will contain the rates only in prescribed tender form (Schedule of Price & Quantity).
- 5. Any tax like GST, Labour Cess etc., if applicable, must be quoted specifically by the tenderer.

(Pravesh Kumar)
SUPERINTENDING ENGINEER (Tech.)
KESCo.

ELIGIBILITY CRITERIA/PRE-QUALIFYING REQUIREMENTS (As per Ref. No. 1651/RESPO/Saubhagya/SBD Dated 25-05-2019 of MD UPPCL) OF TENDER NO. T-10/S.E.Tech/2024-25, OPENING ON 21.03.2025.

A- Technical Requirement:-

- I. The bidder should have a valid Class 'A' Electrical License Holder.
- II. The bidder should have successfully completed the turnkey/semi-turnkey work of the following nature in the last five financial year as prime contractor from the date of opening of bid part-1:-
- 1- Should have successfully erected and commissioned electrical & IT work in a single turnkey/semi turnkey order, having minimum order value of 80% of the estimated cost of the present tender specification, (80% of Rs. 32.50 Lakh i.e. Rs. 26.00 Lakh) or
- 2- Should have successfully erected and commissioned electrical & IT work in maximum two turnkey/semi turnkey order, having minimum order value of 40% each of the estimated cost of the present tender specification, (50% of Rs. 32.50 Lakh i.e. Rs. 16.25 Lakh) or
- 3- Should have successfully erected and commissioned electrical & IT work in maximum three turnkey/semi turnkey order, having minimum order value of 40% each of the estimated cost of the present tender specification. (40% of Rs. 32.50 Lakh i.e. Rs. 13.00 Lakh)

B- Financial Requirement:-

- i) The Minimum Average Annual Turnover (MAAT) for the best Three years out of the last Five Financial years MAAT should not be less than Rs. 32.50 Lakh (100% of the estimated cost, i.e. 100% of Rs. 32.50 Lac) duly Certified/Audited by Chartered Accountant.
- ii) Net worth of the bidder should be positive. Net worth means the sum total of the paid up capital and free reserves (excluding reserves created out of revaluation) reduced by aggregate value of accumulated losses (including debit balance in profit and loss account for current year) and intangible assets, duly Certified/Audited by Chartered Accountant.
- iii) Solvency:- the bidder should have a minimum solvency of Rs. 8.13 Lakh (25% of estimated cost, i.e. 25% of Rs. 32.50 Lac) or credit facility for the same from Nationalized/scheduled bank.
- iv) The bidder shall have to annex character certificate from the District Magistrate along with the Techno Commercial part of the bid document, issued within 3 Months from the date of bid opening.
- **C-** The bidder should not be blacklisted/debarred from business in any Govt./Semi Government/PSU/Local Bodies etc. at the time of bid opening. They have to submit an undertaking regarding this along with the bid.
- D- Certified copy of GST registration of the firm must be enclosed. in Part-I.

E- Self-attested copy of PAN of the firm must be enclosed. in Part-I.

SUPERINTENDING ENGINEER (Tech.) KESCo.

TERMS & CONDITIONS OF TENDER NO. T-10/S.E.Tech/2024-25, OPENING ON. 21.03.2025

- 1. The work will be carried out at site as mentioned in Tender.
- 2. The quantity may vary by 50% on either side.
- 3. The work will be executed under Supervision of concerned Assistant Engineer-Ist, 33 KV & Electrical Safety, Kesco Kanpur & Executive Engineer, 33 KV & Electrical Safety, Kesco Kanpur.
- 4. The rate quoted by the tenderer will be firm in all respect and no variation in plus side will be allowed during contractual period.
- 5. Labour, Vehicle, Crane, All T & P required for the work, will be arranged by the Contractor at his own Cost. Other materials as per schedule-P for the work will be provided by KESCo.
- 6. The contractual period will be 102 Months from the date of contract/LOI awarded to successful tenderer.
- 7. The offer should be valid for at least 03 Months.
- 8. All the damaged/replaced, unused and surplus materials will be the property of KESCo which will be returned by the contractor to KESCo immediately after completion of work.
- 9. Any loss/damage occurred to KESCo during Work will be the responsibility of the contractor and cost of such damages/losses will be payable by the contractor to KESCo.
- 10. The contractor will be fully responsible for any accident occurred to their staff deployed by him for the work. No claim in this regard will be admissible in KESCo.
- 11. The work will be carried out in accordance with direction and design given by the Engineer of contract or his authorized representative.
- 12. Successful tenderer will have to enter in to an agreement with KESCo on prescribed stamp paper at his own cost before commencement of work.
- 13. <u>Contract Performance Guarantee</u>:- The Contract Performance Guarantee shall be 10% of the Contract Value of the tender specifications and in the form of RTGS/NEFT/FDR/DD/Bankers Cheque/BG (from a scheduled bank) (valid for the entire contract + 6 months) only infavor of Dy Chief Accounts Officer, Kanpur Electricity Supply Company Ltd., Kanpur. In any case, the successful bidder shall not be allowed to deduct CPG amount from their running bills and they are required to submit valid & requisite Contract Performance Guarantee.
- 14. Other terms & conditions will be governed by Form, 'A' & 'B' of erstwhile UPSEB.

(Pravesh Kumar)
SUPERINTENDING ENGINEER (TECH.)
KESCo.

SCHEDULE OF GENERAL PARTICULARS

1. Name of the Tenderer :

(a) Head Office address :

(b) Registered Office address :

(c) Postal address of the tenderer :

(d) Fax No. :

(e) E-mail id :

- 2. Name and address of manufacturer of the major equipment's:
- 3. Works
 - (a) Location with full postal address
 - (b) Total Space occupied in sq. meters (approximate with in 5%)
 - (c) Constructed area in sq. meters (approximate with in 5%)
- 4. Name and address of local representative and his telephone number
- 5. Name and address of the officer of the Tenderer / Manufacturer to whom all reference shall be made for expeditious co-ordination.
- 6. Name of foreign collaborator, if any.
- 7. Whether the designs are their own or obtained from other sources. If from other sources the same may be indicated.
- 8. The Name, designation, qualification and experience of the engineer employed by the tenderer in design, development and manufacturing of the quoted equipment.
- 9. Authorized capital of the company.
- 10. Total annual turnover of the firm during last three financial years.
- 11. Actual production per year of the equipment quoted. During last five financial years giving quantity and bill value rounded off two decimal place of Rs. Lacs excluding Central Excise.
- 12. Manufacturing capacity per month of the quoted equipment otherwise.
- 13. State the name and designation of your relative (s) if any working in KESCo.
- 14. 1 % Performance Security in terms of requirement of specification is to be Deposited within 30 days of placement of Order. Whether or not willing to DEPOSIT. If no, state reasons.
- 15. Whether certificates for satisfactory performance of offered equipment enclosed, if yes ,give the quantity to which it refers.

16. Whether quoted ex- works price are firm	Yes/No
17. Whether ex- works prices quoted or not.	Yes/No

18. Whether packing, forwarding fright & insurance Cover (for transit plus 30 days storage thereafter) has been quoted beside ex-works prices (All these charges are to be clubbed)

Yes/No

19. Whether the erection, testing& commissioning prices are quoted or Not 20. Terms of payment as mentioned in relevant clause are acceptable or not Yes/No

21 Give Sales Tax/Trade Tax registration no. (Enclose last clearance certificate)

Yes/No

(1) Central

(2) State

22. Income tax clearance certificate of current and the preceding year enclosed or not

Yes/No

23. Have you ever been declared bankrupt? If yes please give details

Yes/No

24. Whether the tenderer is agreeable to execute the contract in case the deviations stipulated by him are not acceptable to the purchase.

Yes/No

25. Give two reference (Name, Designation and complete postal address) who can rectify Tenderer's financial status and capacity to undertake such works. One of the reference should be from any scheduled nationalized bank in India.

Yes/No

26. Have you offered any discount and if so, then what is the rebate /discount in rupees.

Note: Bidder shall have to demonstrate his offered system within week of intimation by purchaser.

Seal of the Company:

Full Signature: Name of Tenderer: Date:

E-Tender No
From :-
M/s
To, Superintending Engineer (Tech.) 33/11 KV Sub-Station Fazalganj, KESCo., Kanpur.
Dear Sir, With reference to your tender for the above work, I/We offer to submit our proposal having rates for site, erection at site in the schedule annexed or such portion thereof, as you may determine in strict accordance with the terms, conditions and instructions to the tenderer and conditions of the tender and sale contained in Part-1 of the above referred tender to the satisfaction of the seller or in default thereof to forfeit to and pay to (Name of Discom), the sum of money mentioned in the said conditions.
THE RATES QUOTED ARE NET AND FIRM AND IN FULL SATISFACTION OF ALL CLAIMS. I/WE AGREE TO ABIDE BY THIS TENDER FOR THE PERIOD OF 180 DAYS FROM THE DATE OF OPENING OF BID PART-I. A sum of Rsvide nodated bank, in the form of DD/Bankers Cheque or RTGS/NEFT having UTR No Vide (Name of Bank) at ender cost has been Deposited in the Discom account. The proof of the same has been annexed with the bid proposal. A sum of Rsvide nodated bank, in the form of bank, in the form of
on account of earnest money security deposit specified in the said clause of the "Instructions to the enderers". I/We hereby undertake and agree to execute a contract in accordance with the said Terms Conditions & Instruction to the Tenderer' of the tender bid specification.
Firm RTGS Details:- The details of the funds (earnest money/Tender Fees) given by the firm in the present tender, are Deposited in Firm current account number – Name of Bank with address:-
FSC code of the branch –
Amount :- Rs & head (EMD/Tender Cost)
JTR No. Yours faithfully

Signature of the authorized Signatory (With complete address & Seal)

PART-1 <u>DECLARATION</u> (To be executed on a non-judicial stamp paper)

Tender invited by:- Superintending Engineer (Tech.) 33/11 KV Sub-Station Fazalganj, KESCo., Kanpur.
Tender for :- For the work of in the jurisdiction of (Name of Unit) under SE (Tech.) KESCo Kanpur.
Name of tenderer :
Specification No. :
Date of opening of bid part-1:
IN CONSIDERATION of the KESCo having treated the Tenderer to be an eligible bidder whose tender may be considered, the Tenderer hereby agree to the condition that the proposal is response to the above invitation shall not be withdrawn by us within 180 days from the date of opening of the tender (or any extension thereof), also to the condition that if there after the Tenderer does withdraw his proposal within the said period, the Earnest Money deposited by him may be forfeited to the KESCo and at the discretion of the Purchaser, the purchaser may debat the tenderer from tendering for a minimum period of one year reckoned from the date of opening of the tender.
Signed this Day of20
Place

Signed by

State title (whether Proprietor/Partner/ (With complete address & Seal)

SCHEDULE 'G

Part –II

DEVIATIONS FROM "TECHNICAL SPECIFICATION"

All deviations from the "Technical Specification" shall be filled in clause by clause, in this schedule. Compliance with the specifications will be taken as granted if the deviation are not specifically mentioned in this schedule. In case there are no deviation(s) the "NIL" information should be furnished 'In case tenderer is required to accept the standard clause, he should indicate the amount in tender bid part-II schedule P by which the tender price will there by increase/decrease.

Sl.No.	Page No.	Clause No. and Stipulation	Deviation
		in KESCo Specification	

The Tenderer hereby certifies that the above mentioned are the only deviations from the "Technical Specification".

Seal of the Company

Signature: Name: Designation: Date:

SCHEDULE "H" Part -II

DEVIATIONS FROM "INSTURCTIONS TO TENDERERS

All deviations from the "Technical Specification" shall be filled in clause by clause, in this schedule. Compliance with the specifications will be taken as granted if the deviation are not specifically mentioned in this schedule. In case there are no deviation(s) the "NIL" information should be furnished 'In case tenderer is required to accept the standard clause, he should indicate the amount in tender bid part-II schedule P by which the tender price will there by increase/decrease.

Sl. No.	Page No.	Clause No. and Stipulation	Deviation
		in KESCo Specification	

The Tenderer hereby certifies that the above mentioned are the only deviations from the "Instructions to Tenderers".

Seal of the Company

Signature: Name: Designation: Date:

SCHEDULE "I"

Part-I

DEVIATIONS FROM GENERAL REQUIREMENTS OF SPECIFICATION

All deviations from the "Technical Specification" shall be filled in clause by clause, in this schedule. Compliance with the specifications will be taken as granted if the deviation are not specifically mentioned in this schedule. In case there are no deviation(s) the "NIL" information should be furnished 'In case tenderer is required to accept the standard clause, he should indicate the amount in tender bid part-II schedule P by which the tender price will there by increase/ decrease.

Sl. No.	Page No.	Clause No. and Stipulation	Deviation
		in KESCo Specification	

The Tenderer hereby certifies that the above mentioned are the only deviations from the "General requirements of specification".

Seal of the Company

Signature: Name: Designation: Date:

INSTRUCTION TO BIDDERS

1. Definition (s)

In this bid document (including all the appendices), unless the context otherwise requires, the terms given below shall have the following meaning assigned to them:

- **1.1** "Addendum" shall mean any other document issued to the bidders in addition to the bid document by the DISCOM in the context of this bidding process.
- 1.2 "Agency/Service Provider/Contractor" shall mean the successful bidder who has received the Letter of Award and signed the agreement with the DISCOM in the context of this bidding process.
- 1.3 "Award of Contract" shall mean the issue of the Letter of Award/Letter of Intent.
- **1.4** "Bid/Tender" shall mean the proposal/document that the bidder submits in the requested and specified form as mentioned in bid documents.
- 1.5 "Bidder" shall mean the firm/party who quotes the offer against a tender or Expression of Interest.
- **1.6** "Bid documents" shall mean all the documents issued to the bidder to procure works/services/materials.
- 1.7 "BG" shall mean Bank Guarantee.
- 1.8 "Business" shall mean electricity distribution and Revenue collection activities.
- 1.9 "Companies Act" shall mean The Companies Act, 1956 (as amended replaced from time to time).
- 1.10 "Consumer" shall mean any person who is supplied with electricity for his own use by a licensee or the Government or by any other person engaged in the business of supplying electricity to the public under this Act or any other law for the time being in force and includes any person whose premises are for the time being connected for the purpose of receiving electricity with the works of a licensee, the Government or such other person, as the case may be.
- 1.11 "Contract" means the Contract Agreement entered into between the DISCOM and the Agency/servicer/contractor, together with the Contract Documents refereed to therein all such documents shall constitute the contract and the terms Contract shall in all such documents be construed accordingly.
- 1.12 "Contract Value" shall mean the Original contract value, as adjust after giving effect of
 (i) price escalation (as per the statutory provisions), and (ii) changes in statutory taxes
 which is to be compensated by DICOM as per the contractual provisions (if any).

2. Consortium/Joint venture Bidding:-

Consortium bidding/Joint Venture bidding as mentioned in Pre-qualification requirement.

3. Eligible Bidders:-

- 3.1 A Bidder may be an individual, private entity, government-owned entity-subject to clause 5.2 below and shall furnish as part of their unconditional bid, documents establishing the bidder's qualifications to perform the works/services to the satisfaction of the DISCOM/Service Recipient. The detailed eligibility criteria are listed out in Section Eligibility Criteria for Bidders.
- **3.2** Bidders shall provide such evidence of their continued eligibility satisfactory to the EDC DISCOM, as the DISCOM shall reasonably request.

4. Responsibility of bidder(s):-

- **4.1** The DISCOM will not assume any responsibility regarding information gathered, interrelations or conclusions made by the bidder or regarding information, interpretations or deductions the bidder may derive from the data furnished by the DISCOM or any other data.
- **4.2** Verbal agreement or conversation with any officer/employee of the DISCOM either before or after the submission of bid shall not affect or modify any of the terms and conditions or obligations contained herein.
- 4.3 It shall be the sole responsibility of bidders to determine and to satisfy themselves by such means as they consider necessary or desirable as to all matters pertaining to this bidding process including in particular all factors that may affect the cost. Duration and execution of the works/services.

5. Eligibility Criteria:

- **5.1** The bidder (s) shall furnish, as part of their unconditional bid, documents establishing the bidder's qualification criteria are listed out in Eligibility criteria/Pre-Qualification requirement of this bid document.
- 5.2 Notwithstanding anything stated therein, the DISCOM reserves the right inquire and review the bidder's capability and capacity to perform the work during the course of evaluation or after award.

6. Project site visit :-

- 6.1 The bidder is advised to visit and examine the site where the works/service is to be executed and its surroundings, and obtain for himself on his own responsibility all information that may be necessary for preparing the bid, submission of offer and entering into a Contract for execution of works/services. The cost of visiting the site shall be borne by the bidder.
- 6.2 The bidder and any of its authorized personnel shall be granted permission by the DISCOM to enter in its premise (s) and land(s) for the purpose of such inspection, but only upon the condition that the bidder and its personnel shall release and indemnity the DISCOM and its personnel from and against all liability in respect thereof and shall be responsible for death or personal injury, loss of or damage to property.

7. Process to be Confidential

7.1 This bid document and any other document(s) released, information provided, discussions held, etc., as part of the bidding process, is strictly confidential and must not be divulged to anyone who is not directly involved in preparation of the bid, and the bidder(s) shall keep all information within this proposal or gained during the bidding or other processes confidential. No information or publicity will be allowed to any third party unless specific written authorization is obtained from the DISCOM.

8. Clarifications on bid documents

- 8.1 The bidders are expected to be fully conversant with all the clauses of the bid document before responding to it. However, prospective bidder(s) requiring any clarification on bidding documents may notify the DISCOM in writing though email/fax/post, to the address as mentioned in E-tender Notice of this bid document two days prior to the Prebid conference, if any. The queries shall be accepted only from the accredited/authorized officers or executives of the bidder(s).
- **8.2** Pre-bid Conference:- The DISCOM may invite a pre-bid conference in which all prospective bidders are requested to participate. The date, time and place of pre-bid conference is mentioned in the NIT/e-portal. The bidders are requested to send their authorized representatives to attend the pre-bid meetings along with the queries regarding the bid documents, If any. The reply of queries will uploaded on e-portal, only. However, attending the pre-bid conference is not a mandatory requirement for submitting the bid documents.
- 8.3 The DISCOM will respond only to those queries or request(s) for clarification that if receive during pre-bid conference or prior to the scheduled/extended date of submission of bid documents as prescribed by the DISCOM. Replies to the clarifications sought and corresponding amendment(s) to the bid, if any, will be intimated to all bidders through e-portal only. All such clarifications shall form part of the bid documents and shall be incorporated in the bidder's Proposal.
- **8.4** The DISCOM reserves the right to defer/decline responding or addressing to such queries/clarification sought that it feels are inappropriate without assigning any reasons whatsoever.
- **8.5** The copies of all the replies/clarifications issued by the DISCOM shall also be a part of the tender specification.

9. Preparation of Bids :-

- **9.1** The bidder shall submit only one (1) unconditional bid response to this tender/bid document.
- **9.2** The transfer of bid document(s) purchased by one bidder to another is not permissible in any case. Such bids shall be summarily rejected by the DISCOM.
- 9.3 The price bid should be duly filled and signed in accordance with the terms and conditions specified in bid documents thereto for online submission.
- 9.4 All pages of the bid document(s) including conditions of Contract, specifications etc, shall bear the full signatures with official rubber stamp (at the bottom right hand corner of the page) by the bidder. Necessary documents in support thereof must be enclosed with bid documents at the time of submission, failing which bid will be treated as non-responsive and will not be considered. Any bid not bearing signatures on all the documents will stand liable for rejection.
- 9.5 General information, which is not specifically requested for in the bid documents, must be attached separately to the techno-commercial proposal and clearly labeled as "Supporting Material".

10. Deviations from terms and conditions of the bid :-

The bidder must furnish Annex. G. H & I. Performa for "No Deviations" from Terms and Conditions of Bid Document given as Annexure duly filled signed by the authorized signatory of bidder.

11. Bid Forms :-

- 11.1 Wherever a specific form or schedule is prescribed in the bid document, the bidder shall use the same to provide relevant information. If the form or schedule does not provide space for any required information, space at the end of the form or additional sheets shall be used to convey the required information.
- 11.2 For all other cases, the bidder shall design a form to get the required information from the bidder.
- 11.3 DISCOM shall in no case be bound by any printed conditions or provisions in the bidder's bid forms whatsoever.

12. Conditional Bid

- 12.1 The bidders shall offer only unconditional bid as conditional bid are liable to be rejected.
- 12.2 Bidder's printed terms and conditions enclosed with the proposal/offer will not be considered as a part of the Bid under any circumstances whatsoever it may be. These types of bids shall be deemed as conditional bids and shall stand liable for rejection.

13. Deadline for submission of bids

- 13.1 Bids must be submitted on in e-portal only but no later than the time and date as specified in E-tender Notice of Tender Document. In the event of the specified date for submission of bids being declared a holiday for the DISCOM, the bids will be received up to the appointed time on the next working day. Such postponement of date will not have any impact on the other dates specified in the bidding documents (i.e. bid validity and validity of bid security).
- 13.2 The DISCOM may, at its discretion, under intimation to the bidders who have purchased the bidding documents, extend the deadline for the submission of bids/opening of bids by issuing an addendum, in which case all rights and obligations of the DISCOM and bidders previously subject to the original deadline shall thereafter subject to the deadline as extended.

14. Late Bid :-

Bid(s) received by the DISCOM after the bid submission/opening deadline as prescribed in the bid documents will be summarily rejected and shall not be opened to the bidder(s).

15. Withdrawal of Bids:-

The bidder shall not be permitted to withdraw their during the interval between bid submission deadline (as mentioned in e-tender) and the period of bid valid by as per e-tender If any withdrawal of bid is made by the bidder during the above period, it shall result in the forfeiture of the EMD.

16. Associated cost of bid preparation and submission :-

- 16.1 The bidder shall bear all the cost and expenses associated with preparation and submission of its bid including post bid discussions, technical and other presentations,
- 16.2 The DISCOM shall in no case be responsible for or liable to the costs or in DISCOM evaluation of bids, regardless of the conduct or outcome of the bidding process.

17. Request for Modifications/Amendment in Bid Specification:-

17.1 The bidders may request for clarifications or changes in the bid documents by submitting the issues prior to the pre-bid conference date as specified in E-notice tender.

17.2 The DISCOM at their sole discretion may modify the bid documents if deemed appropriate by issuing addendum as a result of a request or clarification discussed during the pre-bid conference.

18. Language of the bid :-

The bid prepared by the bidder and all documents relating to the bid, exchanged between the bidder and the DISCOM shall be written in the English language, provided that any printed literature furnished by the bidder may be written in another language so long as the bid is accompanied by duly certified English translation of its pertinent passages. Failure to comply with this may disqualify a bid. For purposes of interpretation of the bid, the English translation shall prevail.

19. Amendment(s) to bid documents :-

- 19.1 At any time prior to the deadline for submission of the bid or extended date, if deemed necessary, the DISCOM reserves the right to add/modify/delete any portion of bid document by issue of an amendment/addendum, which will be sent to all such bidders, who have indicated their intention to bid. The DISCOM will bear no responsibility or liability arising out of non-receipt of the same in time or otherwise by the bidder. The DISCOM shall assume that the information contained therein will have been taken into account by the bidder in its bid.
- 19.2 The amendment(s) to bid documents shall be binding on all bidders.

(Pravesh Kumår) SUPERINTENDING ENGINEER (Tech.) KESCo., Kanpur

SCHEDULE OF GENERAL INFORMATION KANPUR ELECTRICITY SUPPLY COMPANY LTD. Superintending Engineer (Tech.), 33/11 KV Sub-Station Fazalganj, Kesco, Kanpur. PART-I(A) (To Be submitted with Part Ist of Tender) **Sub-Particulars** Specification No. against which Tender has been TENDER NO. T-10/S.E.Tech/2024-25 Receipt No. & Date by which the tender cost has been Deposit Work of Attending breakdowns, construction, rearrangement, shifting, replacement/repairing of damaged poles etc. of lines and Sub-station apparatus Name of work/material for which tender has against M and R, Small S.I. and Deposit works of 33KV been submitted. Are you the manufacturer of the 3 and 11KV O/H and U/G lines and Sub-station including item ordered for or authorized agent of loading, unloading, carriage, dismantling & erection of manufacturer. power transformer, oil centrifusing (1.5 to 10 MVA) and all related works under the area of Assistant Engineer-Ist, 33 KV & Electrical Safety, Kesco Kanpur Quantity & rates (quote your rate on the schedule of rate & quantity enclosed). Whether the rates are F.O.R. destination/work. Detail of earnest money Deposit 5 What is the validity period of your offer. 6 7 What is the delivery period/completion period. 8 Are the quoted prices firm/firm in all respect. 9 GSTIN of the firm PAN of Firm/Contractor 10 11 Are the quoted prices exclusive/inclusive of GST? Are the quoted prices exclusive/inclusive of 12 Labour Cess if any? Are the quoted prices exclusive/inclusive of 13 Transit Insurance? Have you submitted the list of past supplies/works executed? Give the reference who can certify the financial status and capability to undertake such work. 15 One of the references should be scheduled bank in India.) Do you offer any discount? if yes, so what is the 16 discount unit. Address:-Place Date

(Pravesh Kumar)
SUPERINTENDING ENGINEER (TECH.)
KESCo.

Signature of Contractor With Seal

	PART- I (B)						
	(To Be submitted with Part I st of Tender)						
ई–नि	ई—निविदा सं0 E-Tender No.T-10/S.E.Tech/2024-25 के अन्तर्गत आर.टी.जी.एस किये जाने वाली निविदा						
मूल्य '	मूल्य एवं धरोहर राशि का विवरण जोकि फर्म द्वारा पूर्ण रुप से भरकर जमा किया जाना अनिवार्य है।						
1	ई–निविदा सं0						
2	केस्को का खाता सं0						
2.1	बैक का नाम	Indian Bank					
2.2	शाखा	P.P.N. Market Kanpur					
2.3	खाता सं0	7723508014					
2.4	आई.एफ.एस.सी.	IDIB000K587					
2.5	खाताधारक का नाम	KESCO EMD AND OTHER DEPOSIT A/ C					
3	फर्म का नाम						
4	निविदा प्रपत्र आवेदन मूल्य	₹0 3540.00					
5	यू०टी०आर० सं०						
6	जमा करने की दिनांक						
7	धरोहर धनराशि	₹0 35,000.00					
8	यू०टी०आर० सं०						
9	जमा करने की दिनांक						
	घरोहर राशि वापि	ोस करने हेतु फर्म के खाते का विवरण					
1	फर्म के बैंक का नाम						
2	खाताधारक का नाम						
3	खाते का प्रकार						
4	शाखा						
5	खाता संख्या						
6	आई.एफ.एस.सी.						

(Pravesh Kumar)
SUPERINTENDING ENGINEER (TECH.)
KESCo.

Signature of Contractor With Seal

	Part - II c	of Tender				
		E OF PRICE				
	Kanpur Electricity		any			
S	uperintending Engineer (Tech.), 33/11 k			algani,	Kesco. K	anpur.
2	Name of Work Tender No. Date and Time of sale of Specification	Work of Attending breakdowns, construction, rearrangement, shifting, replacement/repairing of damaged poles etc. of lines and Sub-station apparatus against M and R, Small S.I. and Deposit works of 33KV and 11KV O/H and U/G lines and Sub-station including loading, unloading, carriage, dismantling & erection of power transformer, oil centrifusing (1.5 to 10 MVA) and all related works under the area of Assistant Engineer-lst, 33 KV & Electrical Safety, Kesco Kanpur TENDER NO. T-10/S.E.Tech/2024-25 20.03.2025, 14:00 Hrs.				
			20.0	3.2025.	14:00 Hrs.	
4	Date and Time of receipt of Specification				14:00 Hrs.	
5	Date and Time of opening of specification		21.0	J.202J,	17.00 1113.	
SI.N o	Name of Work		UNIT	Qty	Rate (In Rs.)	AMOUNT
1	Loading, Carriage and unloading of ST poles including old & us store to work site or vice-versa.	ed S.T. Pole from	No.	60		
2	Erection of repaired/new S.T. Pole size 9.0 Mtr. to 13.00 Mtr. crane including digging of Pit back filling and ramming		No.	56		
3	Dismantling of damaged S.T. Pole of very critical position with after removing all the accessories from damaged pole and its including digging of pit or by cutting with gas cutter.	the help of crane all related work	No.	10		
4	Erection of Single/Stud Pole including fitting of all material.		No.	8		
5	Erection of Double pole structure as per standard specifications crane including digging of Pit back filling and ramming		No.	6		
6	Erection of Double pole structure from existing Single Pole in M.S. Channel and other accessories etc.		No.	2		
7	Grouting of pole with cement brick ballast and coarse sand specification including of all civil materials.		No.	64		
8	Making of pole plinth of 400 mm dia, 600 mm height (200m with C.C. in ratio 1:4:8 of cements, stone ballast and coarse sai of materials.	nd including cost	No.	64		
9	Painting of Steel Tubular Pole with one coat of red oxide and t enamel Alm. Paint upto fuse set including cost of all materials.	two coats of first	No.	64		
10	Earthing of pole as per standard specifications		No.	60		
11	Fixing of stay rod and its erection and grouting by fitting of stay and its proper binding and tightening etc.		No.	40		
12	Opening of H.T. Jumpers from the existing 3 Phase 3 Wire H		Job	80		
13	Opening of L.T. Jumpers from the existing 3 Phase 4 Wire L		Job.	16		
14	Loading, Carriage and unloading of ACSR/ Panther Conductor fro		Kg.	1000		
15	Loading, Carriage and unloading of Earth wire/G.l. wire from storvice-versa.		Kg.	196		
16	Laying, stringing, tensioning & final sagging of Earth wire/G.l. wire		Rmt.	360		
17	Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span)		Span	20	-	
18	Dismantling of 33/11 KV V-Type X-arm/M.S Channel/ Guarding Angle/LT Bracket		No.	12		
19	Excavation of ST pole (Old & Used) from ground by digging the pit or by cutting with gas cutter and its proper stacking.		No.	16		
20	Dismantling of binding wire from insulators and loosening of the ACSR mixed conductor on each pole then lowering down the ACSR mixed conductor & rolling into bundles.		Rmt.	360		
21	Taking out 11 KV/0.4 KV cable from drum/complete drum of cal loading carriage and safe unloading by truck/bullock cart at site	of work of vice-	Mtr.	180		
22	Digging of Trench for laying of 11 KV/0.4 KV cable in normal soil wide and 1 to 1.5 meter deep.	in size of 30 cm.	Mtr.	108		

i				
.23	Digging of Trench for laying of 11 KV/0.4 KV cable in kharanja soil in size of 30 cm. wide and 1 to 1.5 meter deep.	Mtr.	36	
24	Digging of Trench for laying of 11 KV/0.4 KV cable in metallic road in size of 30 cm. wide and 1 to 1.5 meter deep.	Mtr.	40	
25	Digging of Trench for laying of 33 KV cable in normal soil in size of 30 cm. wide and 1 to 1.5 meter deep.	Mtr.	116	
26	Digging of Trench for laying of 33 KV cable in kharanja soil in size of 30 cm. wide and 1 to 1.5 meter deep.	Mtr.	108	
27	Digging of Trench for laying of 33 KV cable in metallic road in size of 30 cm. wide and 1 to 1.5 meter deep.	Mtr.	56	
28	Laying of MS Pipe in digged trench.	Mtr.	40	
29	Laying of $11 \text{ KV} / 0.4 \text{ KV}$ XLPE cable in above digged trench covering with bricks and back filling and proper ramming.	Rmt.	60	
30	Laying of 11 KV/0.4 KV XLPE Cable through M.S. pipe in digged trench.	Rmt.	56	
31	Laying of 33 KV XLPE cable in above digged trench covering with bricks and back filling and proper ramming.	Rmt.	380	
32	Laying of 33 KV XLPE Cable through M.S. pipe in digged trench.	Rmt.	60	
33	Making indoor/outdoor joints of 11 KV/0.4 KV XLPE Cable where the cable is being laid.	Job	18	
34	Making indoor/outdoor joints of 33 KV XLPE Cable where the cable is being laid.	Job	36	
35	Making 11 kV/0.4 kV straight through joint including digging of pit upto 1.1 metre depth	Job	10	
36	Making 33 kV straight through joint including digging of pit upto 1.1 metre depth	Job	10	
37	Digging of pit using JCB for making straight through joint 1mx1mx1m	Job	10	
38	Loading, carriage and unloading of Aearial Bunched Cable from store to work site or vice-versa.	Mtr.	16	
39	Laying of HT Aerial Bunched Cable including fixing suspension clamp with eye hook, Dead end clamp with Eye hook on erected Steel Tubular Pole etc.	Mtr.	58	
40	Laying of LT Aerial Bunched Cable including fixing suspension clamp with eye hook, Dead end clamp with Eye hook on erected Steel Tubular Pole etc.	Mtr.	38	
41	Mounting & Erection of single phase distribution box of AB Cable with Piercing Connector, L.T. Bare Neutral Connector, Alu. Lug 25 mm, L.T. Cable 1x25 mm etc.	No.	6	
42	Mounting & Erection of three phase distribution box of AB Cable with Piercing Connector, L.T. Bare Neutral Connector, Alu. Lug 25 mm, L.T. Cable 1x25 mm etc. No.	No.	4	
43	Opening and reconnection of consumer service connections after replacement of line/ poles etc.	dot	25	
44	Erection of Distribution T/F on plinth/D/pole structure.	No.	2	
45	Connection of H.T. Jumper from fuse set to H.T. Bushing of the transformer.	Job	6	
46	Fitting of L.T. D.B. by brackets & clamps on double pole structure & L.T. Cable Connection from T/F Cable to L.T.D.B.	Job	7	
47	Connection of L.T. cable from L.T.D.B to L.T.O.H.	Job	4	
48	Dismantling of existing distribution T/F (Upto 630 KVA)	Job	2	
49	Dismantling of existing distribution T/F Fencing and erection and grouting of T/F Fencing on shifted T/F plinth	Jop	2	
50	Making of H.T. Section points by brackets, clamps & Insulator, tightening of Line, binding of conductor & proper connection.	Job	2	
51	Making of H.T. Jumpers with 3 Phase 3 Wire H.T. O.H. line after erection of work.	Job	2	
52	Making of L.T. Jumpers from 3 Phase 4 Wire L.T. O.H. line for erection work.	Job.	2	
53	Making section in existing Upper Busbar with ACSR Dog/Panther Conductor for dual source supply including mounting of disc insulator string.	Job	4	
54	Loading Carriage, Fabrication & modifications of M.S. Items as per requirement of site conditions.	Kg.	112	
55	Chopping of tree branches lying in the route of HT/LT line touching the tree branches to the phase line conductor making fault to the feeder, for 75mm dia to 450mm dia or as per requirement of site. All arangemant with skiled manpower provided by contractor.	No.	500	
56	Fitting of Cross bracing on double pole structure and related work.	Set	2	
57	Deep Bore GI Pipe Earthing including supply Size GI Pipe 40mm dia B-Class 40 feet long with socket cutter, earth wire 7/14 SWG, Nut & bolts with connection of pipe to distribution T/F Neutral or Body all material shall be provided by contractor with cost of all material.	Job	1	
58	Deep Bore GI Pipe Earthing Including supply ,Size GI Pipe 40mm dia B-Class 80 feet long with socket cutter, 50x6 mm MS flat , nut & bolt, welding work, charcoal , salt with connection of pipe to power transformer neutral or bidy properly . All material shall be provided by contractor with cost of all material.	Job	8	
59	Fabrication, erection & grouting of T/F fencing of frame size 3x2.4 mtr. including cost of M.S. Angle size 40x40x5 and M.S. Flat size 35x5, fixing of welded steel wire fabric on steel frames by welding of 10 SWG wire fabric, including Painting	Mtr2	12	

of Ywo coats of plant on from based surfaces with ready mixed paint to give bus green tabled including cleaning of all and dust. Carriage of all concerning stack material except mentioned above from Kesco. Job 1 Commission of menty excepted network with Kesco mains including testing. Commission of the with version of the same completely. Commission of the with version of the same completely. Loading, Carriage and unloading of 31 KV VCB/CDC (including old & used) from No. 1 Loading, Carriage and unloading of 31 KV VCB/CDC (including old & used) from No. 1 Tables of all 31 KV calls from control of 21 KV VCB/CDC (including old & used) from No. 1 Tables of 31 KV calls from four (complete) from real of the from the state state of work or vice versa. All Tables of 31 KV calls from four complete drawn of earlier from store its loading carriage and safe unloading by truck/bullock cart at site of work or vice versa. Commission of 33 KV calls be some newly except 33 KV VCB after erection work. Commission of 33 KV VCB from unloading point to control room including all related to work. Softling of 31 KV VCB from unloading paint to control room. Softling of 31 KV VCB from unloading paint to control room. No. 2 Softling of 31 KV VCB from unloading paint to control room to loading. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room. No. 2 Softling of 33 KV VCB in certion room with Soft Soft and making earthing as a soft soft soft row with Soft Soft and making earthing as a soft soft soft row with Soft Soft and making earthing as a soft soft soft soft making as a soft soft soft soft soft soft soft s	1	of two costs of				
Scriege of all concerning met material except mentioned above from Kesso. Sore to envise versus. Connecting of newly erected network with Kesco mains including testing. Loading, Carriage and unloading of 3 at V CGOCG (including old & used) from No. 1 Loading, Carriage and unloading of 3 at V CGOCG (including old & used) from No. 1 Loading, Carriage and unloading of 1 at V CGOCG (including old & used) from No. 1 Loading, Carriage and unloading of 1 at V CGOCG (including old & used) from No. 1 Loading, Carriage and unloading of 1 at V CGOCG (including old & used) from No. 1 Loading, Carriage and unloading of 1 at V CGOCG (including old & used) from store its loading of 1 at V CGOCG (including old & used) from store old (including old & used) from control (including old & used) from store old (including old & used) from control (including old & used) from store old (including old & used) from the No. 1 Dismantling of 3 at V CGOCG (including old & used) from unloading old to other common/control room. No. 2 Shifting of 3 at V CGOCG from unloading site to meter comm/control room to loading No. 2 This point of the No. 2 Shifting of 3 at V CGOCG (including old to meter comm/control room to loading No. 2 Erection of 33 NO VCG 8 in control room (including old to meter on old (including old) from the No. 2 Erection of 33 NO VCG 8 in control room (including old) from the No. 2 Erection of 33 NO VCG 8 in control room (including old) from the No. 2 Erection of 33 NO VCG 8 in control room (including old) from the No. 2 Erection of 33 NO VCG 8 in control room (including old) from the No. 2 Erection of 33 NO VCG 8 in control room (including old) from the No. 2 Erection of 33 NO VCG 8 in control room (including old) from the No. 2 Erection of 33 NO VCG 8 in control room (including old) from the No. 2 Erection of 34 NO VCG 8 in control room (including old) from the No. 2 Ere		green shade including closeling of the little and shade including closeling				
Commercing of newly exercted retroin, with Kezo mains including testing. Commissioning and emergization of the same completed: Loading, Carriage and unloading of 33 NV VCR/CCD (including old & used) from No. 1 Loading, Carriage and unloading of 31 NV VCR/CCD (including old & used) from No. 1 Taking out 33 NV Cable from drum/complete drum of cable from store its loading carriage and side unloading by truto/hullock crit at sic of work or vice-versa. Both Commercing of 33 NV Cable box from existing 33 NV VCR bit from store its loading carriage and side unloading by truto/hullock crit at sic of work or vice-versa. Both Commercing of 33 NV Cable box from existing 33 NV VCR bit from store its loading carriage and side unloading by truto/hullock crit at sic of work or vice-versa. Both Commercing of 33 NV VCR bit on on evely verseed 33 NV VCR bit on on the vice-versa. Both Commercing of 33 NV VCR bit on on evely verseed 33 NV VCR bit on on the vice-versa. Both Commercing of 33 NV VCR bit on on evely verseed 33 NV VCR bit on on the vice-versa. Both Commercing of 33 NV VCR bit on on the vice-versa. Both Commercing of 33 NV VCR bit on on the vice-versa. Both Commercing of 33 NV VCR bit on on the vice-versa. No. 2 Shifting of 33 NV VCR bit on on the vice-versa. No. 2 Shifting of 33 NV VCR bit on on the vice-versa. No. 2 Evection of 33 NV VCR bit control room. No. 2 Evection of 33 NV VCR bit control room. No. 2 Evection of 33 NV VCR bit control room. No. 2 Evection of 33 NV VCR bit control room. No. 2 Evection of 33 NV VCR bit control room. No. 2 Evection of 35 NV VCR bit control room of roading searthing of your persent by the vice-versa. No. 2 Evection of 35 NV VCR bit control room with 5006 sq mmM6 flat. Job 2 Evection of 35 NV VCR bit control room with 5006 sq mmM6 flat. Support to every searched 33 NV VCR bit control room for making searthing of your persent by the p	60	Carriage of all concerning stock material except martines delay				
Coading, Carriage and unlocating of 33 xt V Val (NCE) (including old & used) from No. 1 Coading, Carriage and unlocating of 11 KV VCB/LT ACB from Kesco store work site of vice-versa. No. 1 No. 2 No. 1 No. 2 No. 1 No. 2 N			Job	1		
Coading, Carriage and unlocating of 33 xt V Val (NCE) (including old & used) from No. 1 Coading, Carriage and unlocating of 11 KV VCB/LT ACB from Kesco store work site of vice-versa. No. 1 No. 2 No. 1 No. 2 No. 1 No. 2 N	61	Connecting of newly erected network with Kesco mains including testing,	loh			
104-Ing. Cartisga out 38 VX cable from drum/complete drum of cable from store its loading of the cevers. 144 Taking out 33 XX cable from drum/complete drum of cable from store its loading of the cevers. 155 Dismantling of 33 KV cable box from existing 33 XV Jary VEX/DISCO. 156 Dismantling of 33 XV Cable box on newly errected 33 XV Jary VEX/DISCO. 156 Dismantling of 33 XV Cable box on newly errected 33 XV Jary VEX/DISCO. 157 Dismantling of 33 XV Cable box on newly errected 33 XV Jary VEX/DISCO. 158 Dismantling of 33 XV Cable box on newly errected 33 XV VEX after erection work. 158 Shifting of 33 XV Cable box on newly errected 33 XV VEX after erection work. 159 Shifting of 33 XV Cable box on newly errected 33 XV VEX after erection work. 150 Shifting of 31 XV VEX from unloading pile to control room. 150 Shifting of 31 XV VEX from unloading site to meter room/Control room. 150 Shifting of 11 XV VEX from unloading site to meter room/Control room. 150 Shifting of 31 XV VEX from unloading site to meter room/Control room. 151 Shifting of 11 XV VEX from unloading site to meter room/Control room. 152 Shifting of 31 XV VEX from control room. 153 Shifting of 31 XV VEX from control room. 154 Shifting of 31 XV VEX from control room. 155 Shifting of 31 XV VEX from control room. 155 Shifting of 31 XV VEX from control room. 156 Shifting of 31 XV VEX from control room. 157 Shifting of 31 XV VEX from control room control room. 158 Shifting of 31 XV VEX from control room control room control room. 158 Shifting of 21 XV VEX from control room control room control room. 158 Shifting of 21 XV VEX from control room control room control room. 159 Shifting of 21 XV VEX from control room control room control room. 150 Shifting of 21 XV VEX from control room control room control room. 150 Shifting of 21 XV VEX from room room. 150 Shifting of 21 XV VEX from room room room room room room room	62	The same completely	JOB	9		
Taking out 33 kV cable from drum/complete drum of cable from store its loading arrivage and take unloading by truck/bullock cart at site of work or vice-versa. The standard of the standard	62	The term site of vice versa	No.	1		
Taking out 33 kV cable from drum/complete drum of cable from store its loading arrivage and take unloading by truck/bullock cart at site of work or vice-versa. The standard of the standard	63	Loading, Carriage and unloading of 11 KV VCB/LT ACB from Kesco store work site	No	1		
Commenting of 33 NV cable but from existing 33 NV agrice VEXPORE. Job 9	- CA	of vice versa.	140.	1		
Dismantling of 31 KV calle box from existing 31 KV halfs box on newly exected 31 KV calle on No. 9	64	carriage and safe unloading by truck/bullock cart at site of work or vice-versa.	Mtr.	380		
Dismantling of 33 KV indoor type VCB/OCB at control room including all related No. 9	65	Dismantling of 33 KV cable box from existing 33 KV Jarjar VCB/OCB.	Job	9		
Dismantling of 33 KV indoor type VCB/OCB at control room including all related No. 9	66	Connecting of 33 KV Cable box on newly erected 33 KV VCB after erection work.	Job	9		
Shifting of 33 KV VCB from unloading point to control room. Shifting of 33 KV VCB from unloading site to mater room/Control room. No. 2 Shifting of 33 KV VCB from unloading site to mater room/Control room. No. 2 Shifting of 33 KV VCB in control room. Fig. 10 Shifting of 11 KV vCB from unloading site to mater room/Control room to loading point. Fig. 11 KV of 8 used indoor type VCB/OCB from control room to loading point. Firetion and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. No. 2 Frection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. Making isser from existing earth mate of control room for making earthing support to newly erected 33 KV VCB in control room with 50x6 sq mmkh flat. All material provided by contractor including cost of material. Carriage of 11/6 KV KV GF Panels/ Control Panel New & (Cold & used) from Store to Stee of work as and when required or back to store from site. Cold bismantling of carthing of 11/6 KV KV S/F Panels/ Control Panel. Dismantling of carthing of 11/6 KV KV S/F Panels/ Control Panel. Dismantling of carthing of 11/6 KV KV S/F Panels/ Control Panel. Dismantling of connected cable box with S/G Panels. Connection of earthing of 11 KV switchgear Panels with MS flat 50x6 sq mm. All material provided by contractor including cost of material. Mounting of cable box on S/G Panels with handing of concerning cable and its proper floring. Mounting of cable box to line, cable support switchgear panels, section Jobb 2 Dismantling of concerning of mideral connection of which panels with Fixing of Holding Clamp on existing Pinels were ted 57 Pole. Making jumpers from cable box to line, cable support switchgear panels, section Jobb 2 Laying of 11 KV 34105 mm.	67	Dismantling of 33 KV indoor type VCB/OCB at control room including all related	No	0		
Shifting of 11 KV VCB from unloading site to meter room/Control room. Shifting of 33 KV clid & used indoor type VCB/OCB from control room to loading point. Shifting of 11 KV clid & used indoor type VCB/OCB from control room to loading point. Ferction of 33 KV VCB in control room. Roo. 2 Frection of 33 KV VCB in control room. No. 2 Frection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. No. 2 Frection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. No. 2 Frection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. No. 2 Making itser from existing earth mate of control room for making earthing support to newly erected 33 KV VCB in control room with 50% sq mmMS flat. All material provided by contractor including cost of material. To Carriage of 11/6.6 KV S/G Panels/ Control Panel New & (Clid & used) from Store to Site of work as and when required or back to store from site. Dob 2 To Dismantling of tearthing of 11/6.6 KV S/G Panels/ Control Panel. Job 2 Dismantling of connected cable box with S/G Panels/ Control Panel. Job 2 Dening of internal connection to 11/6.6 KV S/G Panels/ Control Panel. Job 2 Dening of internal connection to 11/6.6 KV S/G Panels/ Control Panel. Dob 2 Dopening of internal connection to 11/6.6 KV S/G Panels/ Control Panel. Connection of earthing of 11 K S ASIG Panels/ Control Panels. Connection of earthing of 11 K S ASIG Panels/ Control Panels. Connection of earthing of 11 K S ASIG Panels/ Control Panels. Connection of earthing of 11 K S ASIG Panels/ Control Panels. Connection of earthing of 11 K S ASIG Panels/ Control Panels. Connection of earthing of 11 K S ASIG Panels/ Control Panels. Laying of Cable box on S/G Panels with handing of concerning cable and its proper fibring. Bala Making impers from cable box to line, cable support switchgear panels, section poles of earth plate. Bala Laying of 1 KV S ASIG Dog quant Cable Corte Panel Prole to Pole) with Fixing of Holding Clamp on exist	68					
Shifting of 33 KV old & used indoor type VCB/OCB from control room to loading pols. Shifting of 11 KV old & used indoor type VCB/OCB from control room to loading pols. Fection and grouting of 11 KV VCB/Control Relay Panel in meter room/control Received and grouting of 11 KV VCB/Control Relay Panel in meter room/control Making riser from existing earth mate of control room for making earthing for subject to newly erected 33 KV VCB in control room with 50K6 sq mm/sh flat. All material provided by contractor including cost of material. All material provided by contractor including cost of material. All material grounded by contractor including cost of material. All material provided by contractor including cost of material. All material provided by contractor including cost of material. Bismantling of lands and season of the subject of the su						
point. 1 Shifting of 11 XV old & used indoor type VCB/OCB from control room to loading point. 2 Erection of 33 KV VCB in control room. 72 Erection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. 73 Frection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. 74 Making riser from existing earth mate of control room for making earthing support to newly erected 33 KV VCB in control room with SDAS sq mmMS flat. 75 All material provided by contractor including cost of material. 76 All material provided by contractor including cost of material. 77 Carriage of 11/6.6 KV S/G Panels/ Control Panel New & (COId & used) from Store to Site of work as and when required to that to store from site. 76 Dismantling of jumpering from cable box to line, cable support switchgear panels. 77 Dismantling of connected cable box with 5/G Panel/ Control Panel. 78 Dismantling of connected cable box with 5/G Panel/ Control Panel. 79 Opening of internal connection to 11/6.6 KV S/G Panels. 80 Dismantling of connected cable box with S/G Panels. 81 Dismantling of connected cable box with S/G Panels. 82 Dismantling of connected cable box with S/G Panels. 83 Dismantling of cathing of 11 KV switchgaar Panels with MS flat SDAS sq mm. All material provided by contractor including cost of material. 84 Dismantling of cable box on S/G Panels with handing of concerning cable and its proper fixing. 85 Dismantling of cable box on S/G Panels with handing of concerning cable and its proper fixing. 86 Making jumpers from cable Cable (All size) Over head (Pole to Pole) with Fixing of Mtr. 87 Laying of 11 KV 3-205 sm m Cable Cable (All size) Over head (Pole to Pole) with Fixing of Handing Camp on existing /newly erected ST Pole 88 Dismantling Camp on existing /newly erected ST Pole 89 Laying of 13 KV 3-20-400 sq mm Cable Over head (Pole to Pole) with Fixing of Huffire Camp on existing /newly erected ST Pole 10 Laying, stringing tensioning and binding of Panther conductor for H.T./L.T. O.H.		Shifting of 33 KV old & used indeer type VCP/OCP from sentral	No.	2		
point. 72 Erection of 33 KV VCB in control room. 73 Erection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. 74 Making riser from existing earth mate of control room for making earthing support to newly erected 33 KV VCB in control room with SOKS sq mmMS flat. 75 All material provided by contractor including cost of material. 76 Carriage of 11/6 K KV S/G Panels/ Control Panel New & (Old & used) from Store to Site of work as and when required or box to store from site. 76 Dismantling of Jumpering from cable box to line, cable support switchgear panels. 77 Dismantling of earthing of 11/6 K KV S/G Panels/ Control Panel. 78 Dismantling of connected cable box with 5/G Panels/ Control Panel. 79 Opening of internal connection to 11/6.6 KV S/G Panels. 80 Dismantling of connected cable box with 5/G Panels. 81 Connection of earthing of 11 KV switchgear Panels with MS flat SOKS sq mm. All material provided by contractor including cost of material. 82 Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. 83 Dismantling of cable box on S/G Panels with handing of concerning cable and its proper fixing. 84 All material provided by contractor including cost of material. 85 Holding Jumpers from cable Cable (All size) Over head (Pole to Pole) with Fixing of 11 KV 3x1SS mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of 11 KV 3x1SS mm Cable Cable Cable (All size) Over head (Pole to Pole) with Fixing of 11 KV 3x1SS mm Cable Cable Cable (All size) Over head (Pole to Pole) with Fixing of 11 KV 3x1SS mm Cable Ca	70	point.	No.	2		
Politics Precision of 33 KV VCB in control room. Precision and grouting of 11 KV VCB/Control Relay Panel in meter room/control Processor Proce	71		No.	2		
Erection and grouting of 11 KV VCB/Control Relay Panel in meter room/control room. Making riser from existing earth mate of control room for making earthing support to newly erected 33 KV VCB in control room with 50Ks ay mamMS flat. All material provided by contractor including cost of material. To Carriage of 11/6.6 KV 5/G Panels/ Control Panel New & (Old & used) from Store to Store of Work as and when required or back to store from site. Dismantling of jumpering from cable box to line, cable support switchgear Job 2 Dismantling of pimpering from cable box to line, cable support switchgear Job 2 Dismantling of connected cable box with 5/G Panels/ Control Panel. Job 2 Opening of internal connection to 11/6.6 KV 5/G Panels. Job 2 Opening of internal connection to 11/6.6 KV 5/G Panels. Bi Connection of earthing of 11 KV switchgear Panels with MS flat 50x6 sq mm. All material provided by contracter including cost of material. Expression of earthing of 11 KV switchgear Panels with MS flat 50x6 sq mm. All material provided by contracter including cost of material. Job 2 Monting of cable box on 5/G Panels with handing of concerning cable and its proper fixing. All material provided by contracter including cost of material. Job 2 Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Laying of 11 KV 3X30 sq mm. Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3X30 sq mm. Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 13 KV 3X30 sq mm. Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 13 KV 3X30 sq mm. Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 13 KV 3X30 sq mm. Cable Over head (Pole to Pole) with Fixing of Mtr. 396 Nature of 3 KV 3X120-400 sq mm cable Cover head (Pole to Pole) with Fixing of Mtr. 1	72					
room. Making riser from esisting earth mate of control room for making earthing support to newly erected 33 KV VCB in control room with 50X6 sq mmMS flat. All material provided by contractor including cost of material. All material provided by contractor including cost of material. All material provided by contractor including cost of material. All material provided by contractor flows & COld & used) from Store to Site of work as and when required or back to store from site. To Simantling of Jumpering from cable box to line, cable support switchgear panels. Job 2 Dismantling of connected cable box with S/G Panels/ Control Panel. Job 2 Dismantling of connected cable box with S/G Panels/ Control Panel. Job 2 Dismantling of connected cable box with S/G Panels. Dismantling of connected cable box with S/G Panels. Dismantling of cold/damaged existing 11/6.6 KV S/G Panels. Connection of earthing of 11 KV switchgear Panels with MS flat 50X6 sq mm. All material provided by contractor including cost of material. Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Laying of 11 KV 3x30 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x30 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x30 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x30 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. All provided Dy contractor of the Control of All RV 3x30 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 31 KV 3x30 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying stringing, tensioning a	12		No.	2		
### Support to newly erected 38 KV VGB in control room with 50x6 sq mmMS flat. Job 2	73		No.	2		
All material provided by contractor including cost of material. 75 Loriage of 11/6.6 k VS/G Panels/ Control Panel New & (Oid & used) from Store to Site of work as and when required or back to store from site. 76 Dismantling of jumpering from cable box to line, cable support switchgear panels. 77 Dismantling of earthing of 11/6.6 k VS/G Panels/ Control Panel. 78 Dismantling of connected cable box with S/G Panels/ Control Panel. 79 Opening of internal connection to 11/6.6 k VS/G Panels/ Control Panel. 80 Dismantling of cold/damaged existing 11/6.6 k VS/G Panels. 81 Connection of earthing of 11 k V switchgear Panels with MS flat 50x6 sq mm. All material provided by contractor including cost of material. 82 Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. 83 Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. 84 Laying of 11 k V3 3x70 sq mm Cable Cable (All size) over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 85 Holding Clamp on existing /newly erected ST Pole. 86 Holding Clamp on existing /newly erected ST Pole. 87 Holding Clamp on existing /newly erected ST Pole. 88 Dismantling of Acrising /newly erected ST Pole busing for the North of Pole in the Pole of Pole with Fixing of Holding Clamp on existing /newly erected ST Pole. 87 Holding Clamp on existing /newly erected ST Pole. 88 Dismantling of Acrising /newly erected ST Pole. 89 Laying of 11 k V3 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 80 Laying of 11 k V3 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 81 Laying of 3x V3 x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 82 Laying of 3x V3 x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 83 Dismantling of Holding Clam	7.			_		
Carriage of 11/6.6 KV S/G Panels/ Control Panel New & (Old & used) from Store to tick of work as and when required or back to store from site. 76 Dismantling of jumpering from cable box to line, cable support switchgear panels. 77 Dismantling of earthing of 11/6.6 KV S/G Panels/ Control Panel. 78 Dismantling of connected cable box with S/G Panels/ Control Panel. 79 Opening of internal connection to 11/6.6 KV S/G Panels. 80 Dismantling of old/damaged existing 11/6.6 KV S/G Panels. 81 Connection of earthing of 11 KV switchgear Panels with MS flat 50x5 sq mm. All material provided by contractor including cost of material. 82 Mounting of cable box on S/G Panels with MS flat 50x5 sq mm. All material provided by contractor including cost of material. 83 Mounting of cable box on S/G Panels with MS flat 50x5 sq mm. All material provided by contractor including cost of material. 84 Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. 85 Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. 86 Laying of 11 KV 3x70s sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 86 Laying of 11 KV 3x10s mm. Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 87 Laying of 11 KV 3x200 mm. Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 88 Dismantling of Arait Bunched Cable from I. O. O/H (damage) line. 89 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. 90 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing, tensioning and binding of Panther conductor 91 Laying, stringing, tensioning and binding of Panther conductor 92 Laying, stringing, tensioning and binding of Panther conductor 93 Fixing of guarding by G.I. wire (approximate 5 lacing of each span) 94 Cross lacing of guarding by G.I	/4		Job	2		
to site of work as and when required or back to store from site. 76 Dismantling of Jumpering from cable box to line, cable support switchgear panels. 77 Dismantling of earthing of 11/6.6 KV S/G Panels/ Control Panel. 78 Dismantling of connected cable box with S/G Panels/ Control Panel. 79 Opening of internal connection to 11/6.6 KV S/G Panels. 80 Dismantling of old/damaged existing 11/6.6 KV S/G Panels. 81 Connection of earthing of 11 KV switchgear Panels with MS flat 50x6 sq mm. All material provided by contractor including cost of material. 82 Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. 83 Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. 84 Laying of 11 KV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 85 Laying of 11 KV 3x30 mm. Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 86 Holding Clamp on existing /newly erected ST Pole 87 Laying of 3x KV 3x120-400 sq mm. Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 88 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. 89 Re-sagging of conductor, on old line after erection of pole, binding of conductor sect. 90 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing, tensioning and binding of Panher conductor of H.T./L.T. O.H. Mtr. 11 Laying, stringing tensioning and binding of Panher conductor of H.T./L.T. O.H. Mtr. 12 Laying, stringing, tensioning and binding of Panher conductor of H.T./L.T. O.H. Mtr. 13 Pixing of guarding by G.I. wire (approximate 5 lacing of each span) 5 Pixing of guarding by G.I. wire (approximate 5 lacing of each span) 5 Pixing of guarding by G.I. wire (approximate 5 lacing of each span) 6 Construction of Metallic/RCC road after proper repairing with appropriate materials. 14 Cading, carria	75		loh	2		
Depart Dismantling of earthing of 11/6.6 KV S/G Panels/ Control Panel. Job 2 2 3 3 3 3 3 3 3 3	/3		100			
Dismantling of earthing of 11/6.6 KV S/G Panels/ Control Panel. Dismantling of connected cable box with S/G Panel/ Control Panel. Dismantling of ointernal connection to 11/6.6 KV S/G Panels. Dismantling of oild/damaged existing 11/6.6 KV S/G Panels. Connection of earthing of 11 KV switchgear Panels with MS flat 50x6 sq mm. All material provided by contractor including cost of material. Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Laying of 11 KV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x185 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 13 XV 3x20 on mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 13 XV 3x20 on mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Mtr. 396 Laying of 13 XV 3x20 on mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Mtr. 396 Re-sagging of 3x XV 3x20-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Mtr. 38 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 38 Re-sagging of conductor, on old line after erection of pole, binding of conductor or Rml service. Span 20 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing, tensioning and binding of McSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Gos conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Gos conductor for H.T./L.T. O.H. Mtr. 1160 Exprise of goarding by G.I. wire (approximate S lacing of each span) Span 5 Restoration of Metallic/RCC road afte	76		Jop	2		
79 Opening of internal connection to 11/6.6 KV S/G Panels. 80 Dismantling of old/damaged existing 11/6.6 KV S/G Panels. 81 Connection of earthing of 11 KV switchgear Panels with MS flat 50x6 sq mm. All material provided by contractor including cost of material. 82 Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. 83 Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. 84 Laying of 11 KV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. 85 Halging of 11 KV 3x185 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 86 Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 87 Laying of 33 KV 3x120-400 sq mm Cable Cover head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 88 Dismantling of Aerial Bunched Cable from LT. O/H (damage) line. 89 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. 90 Laying, stringing, tensioning and binding of Weasel conductor for H.T./LT. O.H. Mtr. 10 91 Laying, stringing, tensioning and binding of Post pog conductor for H.T./LT. O.H. Mtr. 1160 92 Laying, stringing, tensioning and binding of Post pog conductor for H.T./LT. O.H. Mtr. 1160 93 Fixing of guarding angle/guarding channel for laying of guarding No 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 94 Cross lacing of guarding by G.I. wire (approximate S lacing of each span) Span 5 85 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. No 1 99 Dismantling of H.T. pilfer proof meter	77		Job	2		
Dismantling of old/damaged existing 11/6.6 KV S/G Pannels. Dismantling of old/damaged existing 11/6.6 KV S/G Pannels. Connection of earthing of 11 KV switchgear Panels with MS flat 50x6 sq mm. All material provided by contractor including cost of material. Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Laying of 11 KV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x185 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 13 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Bismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 386 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 38 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Laying, stringing, tensioning and binding of Panther conductor Art 18 Cross lacing of guarding by G.I. wire (approximate S lacing of each span) Span 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. Construction of plinth for H.T. pilfer proof metering cubical. No 1 Lading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. Frection of H.T. metering cubical on plinth as per standard norms. No 1 Dismantling of H.T. pilfer proof metering cubicle. No 2 Dismantling of H.T. pilfer	78	Dismantling of connected cable box with S/G Panel/ Control Panel.	Job	2		
Connection of earthing of 11 kV switchgear Panels with MS flat 50x6 sq mm. All material provided by contractor including cost of material. Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Laying of 11 kV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 kV 3x70 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 11 kV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 3x V 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 3x V 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Resagging of 3x V 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Bismantling of Alexa Bunched Cable from L.T. O/H (damage) line. Mtr. 72 Resagging of conductor, on old line after erection of pole, binding of conductor etc. Span 20 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Fixing of guarding angle/guarding channel for laying of guarding Year of guarding angle/guarding channel for laying of guarding Polity of guarding angle/guarding channel for laying of guarding Restoration of Metallic/RCC road after proper repairing with appropriate materials. Polity of guarding and unloading of H.T.Metering Cubicle from store to site or vice-eversa. Rection of H.T. metering cubical on plinth as per standard norms. No 1 Dismantling of H.T. piller proof metering cubicle. Polity of the dect	79	Opening of internal connection to 11/6.6 KV S/G Panels.	Job	2		
material provided by contractor including cost of material. Mounting of cable box on S/G Panels with handing of concerning cable and Its proper fixing. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Making jumpers from cable box to line, cable over head (Pole to Pole) with fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Mitr. 396 Mitr. 396 Mitr. 396 Mitr. 38 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mitr. 38 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. Span 20 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 1 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Fixing of guarding angle/guarding channel for laying of guarding You Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) Span 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. Mother 19 Construction of plinth for H.T. piller proof metering cubical. No 1 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. Security of Tri-Pole structure including all fittings and proper alignment. No 3	80	Dismantling of old/damaged existing 11/6.6 KV S/G Pannels.	Job	2		
material provided by contractor including cost of material. Mounting of cable box on S/G Panels with handing of concerning cable and its proper fixing.	81		Job	2		
proper fixing. Making jumpers from cable box to line, cable support switchgear panels, section poles of each phase. Laying of 11 KV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x305 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 13 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 87 Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole 88 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. 89 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. 90 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 91 Laying, stringing tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 1160 92 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 93 Fixing of guarding angle/guarding channel for laying of guarding No 5 Possible of guarding angle/guarding channel for laying of guarding No 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 94 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) 95 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. 100 Erectlon of Tri-Pole structure including all						
poles of each phase. By Laying of 11 KV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. By Laying of 11 KV 3x185 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 13 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Resigning of Start St	82		Job	2		
poles of each phases Alaying of 11 KV 3x70 sq mm Cable Cable (All size) Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole. B5 Laying of 11 KV 3x185 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole B6 Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole B7 Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole B8 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. B9 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. 90 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. 91 Laying, stringing tensioning and binding of Weasel conductor for H.T./L.T. O.H. 92 Laying, stringing, tensioning and binding of Panther conductor 93 Fixing of guarding angle/guarding channel for laying of guarding 94 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) 95 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. No 1 100 Erection of Tri-Pole structure including all fittings and proper allgnment. No 3	83		Job	2		
Fixing of Holding Clamp on existing /newly erected ST Pole. Laying of 11 KV 3x185 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x120-400 sq mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole By Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole By Laying of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 38 By Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. Capan 20 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing, tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Fixing of guarding angle/guarding channel for laying of guarding No 5 Fixing of guarding angle/guarding channel for laying of guarding No 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. Restoration of Metallic/RCC road after proper repairing with appropriate materials. No 1 Construction of plinth for H.T. pilfer proof metering cubical. No 1 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. Rection of H.T. metering cubical on plinth as per standard norms. No 1 Dismantling of H.T. pilfer proof metering cubicle. No 1 Erection of Tri-Pole structure including all fittings and proper allgnment. No 3						
Holding Clamp on existing /newly erected ST Pole Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Bismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 38 Bismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 38 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Fixing of guarding angle/guarding channel for laying of guarding No 5 Fixing of guarding angle/guarding channel for laying of guarding No 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. Mtr. 9 Restoration of Metallic/RCC road after proper repairing with appropriate materials. No 1 Construction of plinth for H.T. pilfer proof metering cubical. No 1 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. Rection of H.T. metering cubical on plinth as per standard norms. No 1 Dismantling of H.T. pilfer proof metering cubicle. No 1 Frection of Tri-Pole structure including all fittings and proper allgnment. No 3	84	Fixing of Holding Clamp on existing /newly erected ST Pole.	Mtr.	396		
Laying of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole R7 Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole R8 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 38 R8-sagging of conductor, on old line after erection of pole, binding of conductor etc. P0 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 P1 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 P2 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 P3 Fixing of guarding angle/guarding channel for laying of guarding No 5 P4 Cross lacing of guarding by G.I. wire (approximate S lacing of each span) Span 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. No 1 P5 Construction of plinth for H.T. pilfer proof metering cubical. No 1 P6 Construction of plinth for H.T. pilfer proof metering Cubicle from store to site or vice-versa. P8 Erection of H.T. metering cubical on plinth as per standard norms. No 1 P9 Dismantling of H.T. pilfer proof metering cubicle. No 1 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	85		Mtr.	396		
Holding Clamp on existing /newly erected ST Pole Laying of 33 KV 3x120-400 sq mm Cable Over head (Pole to Pole) with Fixing of Holding Clamp on existing /newly erected ST Pole Bismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Bismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Bismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Bismantling of Conductor, on old line after erection of pole, binding of conductor etc. Span 20 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Fixing of guarding angle/guarding channel for laying of guarding No 5 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) Span 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. Construction of plinth for H.T. pilfer proof metering cubical. No 1 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. Bismantling of H.T. metering cubical on plinth as per standard norms. No 1 Dismantling of H.T. pilfer proof metering cubicle. No 1 Erection of Tri-Pole structure including all fittings and proper alignment. No 3		Laving of 11 KV 3x300 mm2 Cable Over head (Pole to Pole) with Fixing of		200		
Holding Clamp on existing /newly erected ST Pole Bismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Fixing of guarding angle/guarding channel for laying of guarding No 5 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) Span 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. Construction of plinth for H.T. pilfer proof metering cubical. No 1 Coading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. Rection of H.T. metering cubical on plinth as per standard norms. No 1 Dismantling of H.T. pilfer proof metering cubicle. No 1 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	86	Holding Clamp on existing /newly erected ST Pole	Mitr.	396		
B8 Dismantling of Aerial Bunched Cable from L.T. O/H (damage) line. Mtr. 38 Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. Span 20 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 Span 5 Fixing of guarding angle/guarding channel for laying of guarding No 5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. Restoration of Pilnth for H.T. pilfer proof metering cubical. Construction of plinth for H.T. pilfer proof metering cubical. No 1 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. Rectorating of H.T. metering cubical on plinth as per standard norms. No 1 Dismantling of H.T. pilfer proof metering cubicle. No 3	87		Mtr.	72	17	
Re-sagging of conductor, on old line after erection of pole, binding of conductor etc. 90 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 91 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 92 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 93 Fixing of guarding angle/guarding channel for laying of guarding No 5 94 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) Span 5 95 Restoration of Metallic/RCC road after proper repairing with appropriate materials. No 1 96 Construction of plinth for H.T. pilfer proof metering cubical. No 1 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. No 1 98 Erection of H.T. metering cubical on plinth as per standard norms. No 1 99 Dismantling of H.T. pilfer proof metering cubicle. No 3	88		Mtr.	38		
etc. 90 Laying, stringing, tensioning and binding of Weasel conductor for H.T./L.T. O.H. Mtr. 10 91 Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 92 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 93 Fixing of guarding angle/guarding channel for laying of guarding No 5 94 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) Span 5 95 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. No 1 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. No 1 99 Dismantling of H.T. pilfer proof metering cubicle. No 3			Span	20		
Laying, stringing tensioning and binding of ACSR Dog conductor for H.T./L.T. O.H. Mtr. 1160 1 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 1 Fixing of guarding angle/guarding channel for laying of guarding No 5 1 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) Span 5 1 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 1 Construction of plinth for H.T. pilfer proof metering cubical. No 1 2 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 3 Erection of H.T. metering cubical on plinth as per standard norms. No 1 2 Dismantling of H.T. pilfer proof metering cubicle. No 3 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	89	etc.				
18 Laying, stringing, tensioning and binding of Panther conductor Rmt 18 P3 Fixing of guarding angle/guarding channel for laying of guarding No 5 P4 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) P5 Restoration of Metallic/RCC road after proper repairing with appropriate materials. P6 Construction of plinth for H.T. pilfer proof metering cubical. No 1 P7 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. P8 Erection of H.T. metering cubical on plinth as per standard norms. No 1 P6 Dismantling of H.T. pilfer proof metering cubicle. No 3	90		Mtr.			
Fixing of guarding angle/guarding channel for laying of guarding No 5 94 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) 95 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. No 1 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	91		Mtr.	1160		
94 Cross lacing of guarding by G.I. wire (approximate 5 lacing of each span) 95 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	92		Rmt	18		
95 Restoration of Metallic/RCC road after proper repairing with appropriate materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	93		No			
materials. 96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 90 Dismantling of H.T. pilfer proof metering cubicle. 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	94		Span	5		
96 Construction of plinth for H.T. pilfer proof metering cubical. 97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	95		Mtr.	9		
97 Loading, carriage and unloading of H.T.Metering Cubicle from store to site or vice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	06		No	1		
yice-versa. 98 Erection of H.T. metering cubical on plinth as per standard norms. 99 Dismantling of H.T. pilfer proof metering cubicle. 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3						
99 Dismantling of H.T. pilfer proof metering cubicle. 100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	97	vice-versa.				
100 Erection of Tri-Pole structure including all fittings and proper alignment. No 3	98	Erection of H.T. metering cubical on plinth as per standard norms.	No			
	99	Dismantling of H.T. pilfer proof metering cubicle.	No	1		
101 Erection of four pole structure including all fittings as well as proper No 3	100	Erection of Tri-Pole structure including all fittings and proper alignment.	No			
	101	Erection of four pole structure including all fittings as well as proper	No	3		

	alignment of structure.				
102					
103	Painting of M.S. structures fitted on pole such as channel, angle, brackets Erection of O/D type Metering unit on D/P Structure.	No	12		
	Loading, carriage & unloading of O/D type metering unit from store to site &	No.	2		
104	vice-versa.	Job	2		
105	Disconnection of H.T./L.T. Lines, Shifting of T/F from ground/plinth to a safe place for construction of T/F plinth.	Job	1		
106	Shifting of T/F from ground to plinth or vice versa and re- connection/disconnection of H.T. L.T. Lines as well as earthing for proper completion.	Job	1		
107	Construction of T/F plinth, suitable for mounting of distribution transformer. Size of the plinth will be 1.2 x 1.2 x 1.2 meter solid with brick work. 75 mm thick C.C. in ratio 1:4:8 with cement, coarse sand and brick ballast laid on the base and 75 mm thick done on all the exposed sides to the plinth.	Mtr3	1		
108	Fabrication and Erection of X-bracing on Four pole structure with fixing of bracing clamp.	Set	4		
109	Fabrication of Isolator structure with M.S. Channel, M.S. Angle, M.S. Flat etc. in required size and length including cutting, drilling holes, welding and assembling as per drawing.	Job	4		
110	Erection and grouting of Isolator structures with 1:4:8 CC 25 mm brick ballast in required size in proper alignment and making plinth of all structure in 1:2:4 CC mix with 20 mm stone grit, 15 Cm ground level to smooth finish and its proper curing including cost of cement.	Job	4		
111	Erection of 33 KV Line Isolator equipment on erected structure in proper alignment.	Job	4		
112	Erection of 33 KV Bus Isolator equipment on erected structure in proper alignment.	Job	5		
113	Loading, Carriage and unloading of Isolator from Kesco. Store to site of work or work site to store including old & damage materials.	Job	3		
114	Earthing of Isolator Structure or other MS structure with M.S. Flat by welding and connecting to existing earth mate of yard.	Job	4		
115	Fabrication of Post Insulator/L.A./C.T/P.T Structure.	No	2		
116	Fabrication of Cable Support Structure.	No	2		
117	Fabrication of Earthing Electrodes 3 mtr. long with 40 mm dia M.S. Round Bar	No	4		
118	making one end pointed upto 15 Cm. Fabrication of Busbar Gantry	Job	2		
119	Fabrication of Neutral Support Structure.	No	2		
120	Erection of Post Insulator/L.A./C.T/P.T Structure.	No	, 2		
121	Erection of Cable Support Structure.	No	2		
122	Erection of Busbar Gantry with the help Crane.	Job	2		
123	Erection of Neutral Support Structure.	No	2		
124	Erection of 33 KV L.A.	No	3		
125	Erection of Post/Pin Insulator with E clamp in Post Insulator Structure/Cable Support Structure.	No	3		
126	Erection of 33 KV C.T/P.T with the help of Crane.	No	3		
127	Erection of CT/PT junction box	No	20		
128	Lowering of ACSR dog Conductor of 33 KV single line for adjusting of V cross arm of single Ckt. line for converting double Ckt. line.	Mtr.	40		
129	Fixing of V-Type cross arm on erected/existing double/try/four pole.	No	7		
130	Fixing of M.S. Channel on erected/existing double/try/four pole.	No	8		
131	Fixing of M.S. Angle on erected/existing double/try/four pole.	No	7		
132	Fixing of G.I. Pin and Pin Insulator on erected/existing double/tri/four pole.	No	20		
133	Opening the binding for taking out the conductor and dismantling the concern X-arm/bracket from pole/rail.	No	7		
134	Dismentalling of existing Jarjar Al. Conductor from existing damaged O.H. Line	Mtr.	40		
135	Painting of Post Insulator/L.A./C.T/P.T Structure.	No	12		
136	Painting of Isolator Structure.	No	11		
137	Painting of Cable Support Structure.	No	4		
138	Painting of Busbar Gantry	Job	2		
139	Painting of Neutral Support Structure.	No	2		
140	Loading, Carriage and Unloading of 33 KV C.T/P.T. from store to site and vice	No	3		
141	Loading, Carriage and Unloading of 33 kV single CRP from store to site and vice	No	1		
142	versa Loading, Carriage and Unloading of 33 kV double CRP from store to site and vice	No	2		
	versa	_		-	

1	Loading Carriago and Unloading of D. U.S. L. C.				
143	Loading, Carriage and Unloading of Rail Pole for bus bar gantry from store to site and vice versa	No	2		
144	Loading carriage & unloading of main tank of 3/5/6/8/10 MVA, 33/11 KV power T/F alongwith radiators & its all accessories & material of following T/F from store to site of work or worksite to store in between 20 Km. distance.	No.	2		
145	Shifting of Pilfer proof metering cubical from site to meter room.	No.	2		
146	Erection of C.T./P.T. O.D. unit on erected double pole.	No.	2		
147	Mounting of 33 KV Pin Insulator	No.	8		
148	Mounting of 11 KV Pin Insulator	No	8		
149	Mounting of 11 kV B&S type Disc Insulator	No	20		
150	Digging of Pit 2x2x1 mtr. for laying of cable through HDD Method.	No.	2		
151	Laying of 33/11 KV 3x300/400/185/120/70 sq.mm XLPE with HDPE Pipe through HDD Method and also marking feeder name on pipe with Paint at the interval of each 100 mtr. Along with supply of pipe	Rmt.	20		
152	Laying of 33/11 KV 3x300/400/185/120/70 sq.mm XLPE without HDPE Pipe through HDD Method and also marking feeder name on pipe with Paint at the interval of each 100 mtr.	Rmt.	20		
153	Repairing of 33 KV Old Isolator by replacing the jaws, operating mechanism and blades or by oiling and greasing of moving parts or by adjustment of moving mechanism or by leveling the whichever is required for smooth operation of isolator and its all related work.	Job	7		
154	Dismantling of 33 KV outdoor CT/PT with the help of Crane.	No.	2		
155	Erection of Lower Bus bar with ACSR Panther/DOG conductor	Job	2		
156	Erection and Grouting of 33 KV VCB Structure on Plinth	Job	2		
157	Erection of 33 KV VCB on erected structure with the help of Crane.	Job	2		
158	Erection of 33 KV single control relay panel in control room	Job	2		
159	Erection of 33 KV double control relay panel in control room	Job	2	9	
160	Pegging of 3 mtr. long Earth Electrodes 40 mm dia in to ground by hammering	No.	3		
161	keeping its head 0.5mtr. below the ground level. Laying of earthing strip of 50x6 mm M.S. Flat after cutting, bending, shaping and welding with earth electrodes with welding of 'U' Clamps on each electrodes and making proper joints overlapping with 40 cm each other it includes welding of riser from making earth mate to structure of both side.	Rmt.	18		
162	Laying of 40 mm2 M.S. rod after cutting bending, shaping and welding with earth electrodes with welding of U clamps on each electrode and making proper joint overlapping 15 Cm each electrode for main earthmate.	Rmt.	20		
163	Erection of new Upper Busbar with ACSR Dog/Panther Conductor including mounting of disc insulator string.	Job	2		
164	Making of 33KV V.C.B. plinth in size of 1.5x2.4x1.0 meter with brick work cement, sand ratio 1:6 making proper pockets for anchor bolts grouting its plastering around with smooth finish including cost of civil material.	No.	2		
165	Connecting of main earthing of control room & jointing with switch gear panel by welding of M.S. flat size 50x6 mm including all materials.	Job	20	,	
166	Filling of soil for leveling of S/S Switch yard as per site requirement.	Mtr3	40		
167	Final leveling of yard and removal of wastage material and soil from switch yard.	Job	2		
168	Proper Earthing of Power T/F at three points by extending the existing M.S. Flat 50x6 mm with main earth mat by welding properly. All material provided by contractor including cost of material	Job	2		
169	Fitting of 3 mtr. Long 2 No. rail pole on power T/F plinth during erection of power transformer.	Job	3		
170	Dismantling of Rail Poles of existing bus bar gantry	Job	2		
171	Dismantling of Upper Bus Bar	Job	3		
172	Dismantling of lower bus bar	Job	2		
173	Erection of TPMO	No.	2		
174	Dismantling of TPMO	No.	2		
175	Dismantling of 33 kV Isolator	No.	5		
176	Unmounting of Pin/Disc Insulator	No.	5		
177	Making of 11/33 kV Fuse Point	Job	3		
178	Laying of 1st class bricks after proper ramming of soil including cost of materials.	mtr2	40		
179	Filling of sand above laid bricks on edge including cost of materials.	mtr2	44		
	Loading, carriage & unloading of distribution Transformers (Upto 630 KVA) from				
180	Store to site, site to site & vise-versa. Unloading of following power T/F main tank filled with oil, along with its all	No.	1		
181	accessories like radiators, conservator tank T/F oil vent pipe etc. from Truck by crane and proper stacking.				

1 101 1	10/0/5 http://doi.org/10.15			
181.1	10/8/6 MVA, 33/11/6.6 KV T/F with 2 No crane	Nos.	2	
181.2	5/3/1.5 MVA, 33/11/6.6 KV T/F	Nos.	2	
182	Dismentalling of following power T/F including draining of T/F oil from radiators if necessary dismentalling of all accessories, as Radiators, vent pipe conservator Tank from main Tank of T/F (Either one or all) and its proper stacking.			
182.1	10/8/6 MVA, 33/11/6.6 KV T/F	Nos.	2	
182.2	5/4/3 MVA, 33/11/6.6 KV T/F	Nos.	3	
182.3	10/8/6 MVA, 33/11/6.6 KV T/F with 2 No crane	Nos.	2	
182.4	5/4/3 MVA, 33/11/6.6 KV T/Fwith 2 No crane	Nos.	2	
	Shifting of T/F Tank Empty/filled by dragging or by crane of following	,,,,,,,		
183	running/damaged T/F from unloading point to plinth of T/F or from T/F plinth to shifting/loading point distance upto 25 meters and its placing in proper alignment on plinth of Transformer.			
183.1	8/6 MVA, 33/11/6.6 KV T/F	Nos.	2	
183.2	5/4 MVA, 33/11/6.6 KV T/F	Nos.	3	
183.3	10/8/6 MVA, 33/11/6.6 KV T/F with 2 No crane	Nos.	2	
183.4	5/4/3 MVA, 33/11/6.6 KV T/F with 2 No crane	Nos.	2	
183.5	3/1.5 MVA, 33/11/6.6 KV T/F	Nos.	2	
184	Loading carriage & unloading of main tank of T/F alongwith radiators &its all accessories & material of following T/F from store to site of work or worksite to store in between 20 Km. distance.			
184.1	8/6 MVA, 33/11/6.6 KV T/F	Nos.	2	
184.2	5/4 MVA, 33/11/6.6 KV T/F	Nos.	3	
184.3	10/8/6 MVA, 33/11/6.6 KV T/F with 2 No crane &trolla	Nos.	2	
184.4	5/4/3 MVA, 33/11/6.6 KV T/F with 2 No crane &trolla	Nos.	2	
184.5	3/1.5 MVA, 33/11/6.6 KV T/F	Nos.	2	
185	Erection of radiators, conservator tank vent pipe and all other accessories on main tank of following T/F including oil filling and all related work.			
185.1	10/8/6 MVA, 33/11/6.6 KV T/F	Nos.	2	
185.2	5/4/3 MVA, 33/11/6.6 KV T/F	Nos.	3	
185.3	10/8/6 MVA, 33/11/6.6 KV T/F with 2 No crane	Nos.	2	
185.4	5/4/3 MVA, 33/11/6.6 KV T/F with 2 No crane	Nos.	2	
186	Dismantling of earthing of running/damaged transformer at two points with the help of gas cutter.	Job	2	
186	Dismantling and taking out the cable support structure by cutting with gas cutter for shifting of T/F including cutting of earthing of cable support structure wherever is required including its all related work.	Job	. 2	
186	Dismantling and taking out the neutral support structure by cutting with gas cutter alongwith removing of flexible copper bond and its proper stacking.	Job	2	
186	Erection and welding of cable support structure with the help of welding including earthing of support in proper alignment and all related work.	Job	2	
186	Erection & welding of neutral support structure with the help of welding including earthing in proper alignment and all related work and fixing of flexible copper bond.	Job	2	
186	Earthing of T/F at two points by extending the existing M.S. Flat size 50x6 mm with main earthmate by welding. All material provided by contractor	Job	2	
186	Fabrication of neutral support structure with M.S. Angle and M.S. Flat.	Job	2	
186	Erection and grouting of neutral support structure with 1:4:8 CC ratio in proper alignment and plinth 15 Cm. above ground level and smooth finish.	Job	2	
186	Fabrication of isolator structure as per standard design.	Job	3	
186	Erection and grouting of Isolator structure in proper alignment and making plinth 15 Cm. above ground level with smooth finish.	Job	3	
186	Construction of power T/F plinth suitable for $5/10$ MVA 33 KV T/F in size of 3 x 3 x 1.5 Mtr. Digging of pit in size of $3.5 \times 3.5 \times 1.2$ Mtr. Of CC work at bottom in size of $3.5 \times 3.5 \times 1.5$ Mtr. With ratio of $1:4:8$ its proper ramming and curing thereafter brick work in size of $3 \times 3 \times 0.8$ Mtr. with $1:6$ CC Sand ratio, thereafter CC work on top in size of $3 \times 3 \times 0.8$ Mtr. thereafter plastering all around the open portion, grouting of rail and M.S. Angle in top CC work and its	Job	2	
186	proper curing. All civil material provided by contractor. T/F Flexible copper bond 30mm vide 30 Cm long & connecting with neutral	Nos.	2	
	support to T/F neutral bushing & proper tightening.			
186	Supply and Erection of HTPB	No.	1	
186	Repairing of damage of H.T./L.T. S.T. Pole comprising following works:-			
187.1	Opening the binding for taking out the conductor and dismantling the concern X-arm/bracket from pole/rail.	Nos.	3	

187.2	Taking out the damaged pole from ground by digging the pit or by cutting with gas cutter and its proper stacking.	Nos.	3		
187.3	Repairing of damaged S.T. Pole by providing M.S. ANGLE 65x65x6 mm(3 feet), Ms pole Clamp with Nut & Bolt(Clamping of both Ends), Concreting for Grouting and Muffing of pole with all material (2FEET Grouting And 1 feet Muffuing) and its welding including its all related work. All material provided by contractor.	Nos.	46		
187.4	Erection of repaired/new S.T. Pole size 9.0 Mtr. to 13.00 Mtr. including digging of Pit back filling and ramming.	Nos.	8	,	
187.5	Mounting of 33 KV, 11 KV & L.T. X-arm/bracket on the pole/rail.	Nos.	7		
187.6	Dismantling /Replacement of 33KV or 11KV pin insulator with G.I. Pin from damaged pole/ X-arm opening of binding from Insulator.	Nos.	10		
187.7	Repairing of 33 KV or 11KV damaged X-arm and proper shaping including drilling of holes whatsoever is required with the help of gas healing and welding.	Job	2		
188	Centrifusing of T/F Oil of Power Transformer.	Ltr.	6000		
189	Digging of cable trench for taking out old/damaged XLPE/PILCA, 3x50 to 3x400sqmm 33/11KV cable & taking out the above Cable from digged trench and back filling of digged trench and relaying the same cable.	Rmt.	4		
190	Making special pole plinth of double pole of size 2 mtr. x0.5 mtr. Including all civil material.	No.	2		
191	Erection of ST pole 16 Mtr. Long including all accessories and hardware fitting as per standard specification.	No.	2		
192	Erection of pale fencing of substation switchyard as per standard specification including cost of material .All material provided by contractor.	Mtr ²	6		
		Total			

(Pravesh Kumar)
SUPERINTENDING ENGINEER (Tech.)
KESCo.

Signature of Contractor With Seal